



Shelby County Government

MARK H. LUTTRELL, JR.
MAYOR

July 8, 2013

TO ALL BIDDERS:

RE: **Addendum No. 2 to Sealed Bid # I-000220**
Ward Road Bank Repair Project

Please note the following revisions and clarifications to the above referenced project:

1. Question: Is it your intention to divert the river around the work site?
2. Answer: Big Creek is a large creek with intermittent flows but exponentially smaller than what we would define as a river. As stated in the pre bid conference the project is being bid in the summer during the dry season to minimize the amount of water in the creek.

The means and methods used by a contractor are usually left to him/her as long as he/she achieves the specified result and complies with all local, state and federal requirements, such as environmental permits. There will be some dewatering required but it is anticipated to be done without the use of cofferdams. Dewatering of the hole with pumping and placing the rock partially with some plastic over it and then dirt fill may be a workable option.

A small berm with a small pipe could also be used to divert any low flow around opposite toe of the creek. Again the contractor should utilize means and methods he/she is most comfortable using.

If you have any questions, please contact Mr. Nelson Fowler at 222-2250.

Sincerely,

James M. Crook E.I.

Shelby County Roads, Bridges & Engineering Department

Cc: Darren Sanders, P.E.

Nelson Fowler

File